Bruhath Bangalore Mahanagara Palike

15

(5)

Office of the Executive Engineer
Electrical Division, Dasarahalli Zone
Bruhath Bengaluru Mahanagara Palike

"DTS for Kind Approval"

Name of the Work:- Providing timer switches to electrical street light installations at ward no-14

Sl. No.	Approved Qty	Description	Unit	Approved Rates		Rate quoted by contractor	
				in Figures	in words	in Figures	in words
		KPWD (Ele) S.R.2010-11					
1	150000	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	sqcm	0.33	Rupees Zero Only Paise Thirty Three Only		
2	20	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete c) 63 Amps	Each	219.00	Rupees Two Hundred and Nineteen Only		
3	20	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	7515.00	Rupees Seven Thousand Five Hundred and Fifteen Only		
4	20	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. b) 40-63 Amps SP 1) Group 'A'	Each	370.00	Rupees Three Hundred and Seventy Only		
5	23	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947. c) 60-70 Amps	Each	3865.00	Rupees Three Thousand Eight Hundred and Sixty Five Only		
6	40	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a) a) 40x40x6mm	Rmtr	240.00	Rupees Two Hundred and Forty Only		
7	200	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV ClassI. Class 'A' PVC Cable d) 4 core 16sqmm	per mtr	150.00	Rupees One Hundred and Fifty Only		
8	200	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required.II. On wall /Structure a) 6 sqmm to 16sqmm	Rmtr	18.00	Rupees Eighteen Only		

9	160	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 16 sqmm	Each	14.00	Rupees Fourteen Only		
10	2.5	Supplying.....amps rated 3 phase with neutral bus bar using requirement capacity electrolytic aluminium strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on powder coated 40x6 mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete.100Amps 4x30x6mm Alluminium Strips	Rmtr	1600.00	Rupees One Thousand Six Hundred Only		

I am prepared to take up the above work at the rates quoted in the Schedule 'B'

CONTRACTOR

EXECUTIVE ENGINEER (Ele)
DASARAHALLI ZONE, BBMP

"DTS Approved"